3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoring Kenchanahalli minor tank, in default of which, tenders will be rejected

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for restoring Kenchanahalli Minor Tank, Reg. No. 69, of Nelamangala Taluk.

No.	Items of work	Per	Quantity	Rate
	BUND.			Rs. a. p.
1	Earthwork cutting grips to bund	C.yds.	776	
2	Do to bund with consolidation	,,	3,859	
3	Silt clearing	,,	226	
4	Earthwork, breach filling with watering and tamping	,,	2,318	
5	Puddle wall in clay	,,	313	
6	Turfing	S.yds.	4,357	
7	Old stone revetment with new jelly	C.yds.	60	
8	New stone revetment	,,	388	
9	Providing new grade stones	Each	18	
10	Do top width stones	,,	18	
11	Do Reg. No. stone	,,	1	
12	Do B M. stones	,,	2	
13	Do gauge stone	,,	1	
	WASTE WEIR			
1	Earthwork	C.yds.	300	
2	Concrete in surki mortar	C.ft.	253	
3	Burnt brick in surki mortar	,,	1,475	
4	Burnt stone slabs roughly dressed	S.ft.	218	
5	Plastering with surki mortar	Sqr.	12·21	
6	Removing and re-setting old stone work with new jelly	C.yds.	97	
7	New stone work	,,	60	
	SLUICE.			
1	Repairing the existing sluice and providing a new pipe sluice, etc.	L. S.	..	

S. SRINIVASA AIYAR,
Executive Engineer.

GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Notice dated 19th October 1925.

Notice is hereby given that sealed tenders will be received at the office of the Chief Electrical Engineer to the Government of Mysore, Bangalore, up to 26th November 1925, for constructing a Dispensary with In-patients ward, Out-houses and etc., at Sivasamudram. The tenders will be opened in public at 2 P.M., on the 28th November 1925. The work should be completed within eight months from the date of acceptance of the tender.

2. The plans, detailed estimate and conditions may be obtained at the Chief Electrical Engineer's Office, Bangalore, between the hours of 11 A.M. and 5 P.M. on all the working days or at the office of the General Superintendent, Generating Station, Sivasamudram, between 8 A.M. and 4 P.M., on all working days.

3. Tenders will be submitted on printed forms, which may be obtained from the office of the Chief Electrical Engineer or the General Superintendent, Sivasamudram. The tenders should be accompanied by a statement in the form given below showing the rates, in figures and words, at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for constructing a dispensary with inpatients' wards, outhouses and etc., at Sivasamudram", in default of which, tenders will be rejected.

5. The Chief Electrical Engineer reserves the right to accept or reject any tender, or any portion thereof, without assigning any reasons whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board in the Chief Electrical Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money of rejected tenders will be returned.

9. The construction work should be started within fifteen days from the date of notification of the acceptance and completed within eight months from the same.

10. Any other conditions that the contractor may wish to state should also be included in his tender.

11. Specification for work is the same as those contained in the Public Works General No 14.

12. The quantities given below are approximate :—

No.	Items of work	Per	Dispensary	Dead House	Kitchen	Latrine
			Quantity	Quantity	Quantity	Quantity
1	Earthwork excavation and filling in basement ..	C.yd.	151	25	8	4
2	Chunam concrete, foundation	C.ft.	1504	203	....	....
3	Stone in mortar foundation and basement ..	C.ft.	3905	351	232	119
4	Burnt brick in mortar, superstructure	C.ft.	7280	377	279	242
5	Burnt stone slabs 6" thick exposed parts roughly dressed.	S.ft.	1426	512	34	....
6	Burnt stone slabs 3" thick roughly dressed ..	S.ft.	....	43	....	....
7	Burnt brick in mortar, archwork with centerings ..	C.ft.	34	....	....	....
8	Chunam plastering 2 coats, Square	Sqr.	119·15	6·31	5·60	4·43
9	Pointing with cement with thread lines	"	8·46	....	....	....
10	Pointing with Chunam with thread lines	"	....	....	0·64	0·45
11	White and colour washing, 2 coats ..	"	124·60	6·95	6·05	4·43
12	Dental parapet wall complete	R.ft.	128	....	....	....
13	Cornice 9" projection	"	128	....	....	....
14	Mangalore tile flooring 9" square on 3" concrete and cement pointed.	Sqr.	13·00	....	....	....
15	Cuddapah slab flooring on 3" of concrete and cement pointed.	Sqr.	....	1·44	0·70	0·50
16	Marble flooring tiles on 3" concrete and cement pointed	Sqr.	1·77	....	....	....
17	Balcony outside windows	Each	6	....	....	....
18	Cutstone pillars 3" x 8" including base and capital ..	Each	13	....	....	....
19	Cornice to Gothic windows	"	1	....	....	....
20	Dado work with white tiles	Sqr.	2·83	....	....	....
21	Madras Terrace roofing 9" thick complete ..	Sqr.	4·50	....	....	....
22	Roofing with first class Mangalore tiles on teak reepers 2" x 1".	"	34·23	3·87	2·14	....
23	Roofing with first class Mangalore ceiling tiles only ..	"	10·36	....	....	....
24	Ridge tiles set in mortar	R.ft.	117	....	....	....
25	Ventilating tiles set in mortar	Each	....	4	4	....
26	Teakwood ornamental finals large	"	....	2	2	....
27	Planking and Zinc guttering to valleys 3' width ..	R.ft.	30	....	....	....
28	Ornamental Eave Boarding with finals (9" x ¾") ..	"	490	79	58	....
29	I Beams put up complete	Cwt.	17·36	....	....	....
30	Teakwood work with wood oiling, 2 coats	C.ft.	207·00	30·80	12·17	....
31	Teakwood panelled doors 1¼" thick with bolts, hinges and locks etc., complete	S.ft.	474	10·5	13·75	....
32	Teakwood panelled windows 1¼" thick shutters with glazed inner shutters and 6 iron bars ¾" dia. complete	S.ft.	490	....	....	....
33	Teakwood windows with panelled shutters 1¼" thick with iron bars ¾" dia. complete.	S.ft.	....	10·5	2·62	....
34	Teakwook glazed Gothic windows without iron bars as per design.	Each	1	....	....	....
35	Teakwood glazed ventilators with iron bars ..	S.ft.	146	....	....	....
36	Silicate painting, 3 coats	Sqr.	29·32	0·67	0·45	....
37	Honey comb work	Sqr.	....	2·41	....	....
38	Tarring, 2 coats	"	....	....	....	2·42
39	Brick in mortar coping over compound wall ..	R.ft	....	....	....	39

S. G. FORBES,
Chief Electrical Engineer.